Remote commissioning GFCH-1-G-R Part number: 8136845



Data sheet

General operating condition

Feature	Value
Scope of services	Data backup and documentation Introduction to the Festo Automation Suite software Configuration and parameterization Remote support during commissioning of 1-axis systems with a safety module Test of system Checking of electrical connections and of travel path
Work involved on site	3 hours of work
Customer requirements	Qualified personnel responsible for the machine must be present on the agreed date YJKP kit must be assembled mechanically 24 V logic and 230/400 V load voltage must be made available Switch and Ethernet cable must be available Local installation of FFT-software (see Support Portal) Local administrator rights Local installation of TeamViewer or Bomgar communication software Stable internet connection
Provision of services	8-10 days subject to agreement

FESTO