Remote commissioning GFCH-1-R

Part number: 8136842



Data sheet

Provision of services

Feature Value Scope of services Data backup and documentation Introduction to the Festo Automation Suite software Configuration and parameterization Remote support during commissioning of 1-axis systems Test of system Checking of electrical connections and of travel path Work involved on site 2 hours of work Customer requirements Qualified personnel responsible for the machine must be present on the . agreed date YJKP kit must be assembled mechanically 24 V logic and 230/400 V load voltage must be made available Switch and Ethernet cable must be available Local installation of FFT-software (see Support Portal) Local administrator rights Local installation of TeamViewer or Bomgar communication software Stable internet connection

8-10 days subject to agreement

General operating condition

8/8/24 - Subject to change - Festo SE & Co. KG

