## Remote commissioning GFCH-2-R Part number: 8136843





**Data sheet** 

General operating condition

Feature	Value
Scope of services	Data backup and documentation Introduction to the Festo Automation Suite software Configuration and parameterization Remote support during commissioning of 2-axis systems Test of system Checking of electrical connections and of travel path
Work involved on site	3.5 hours of work
Customer requirements	Qualified personnel responsible for the machine must be present on the agreed date YJKP kit must be assembled mechanically 24 V logic and 230/400 V load voltage must be made available Switch and Ethernet cable must be available Local installation of FFT-software (see Support Portal) Local administrator rights Local installation of TeamViewer or Bomgar communication software Stable internet connection
Provision of services	8-10 days subject to agreement